

**Cold Weather Procedures
For
Air Pressure Testing
With
PEX Piping**

Air pressure testing of PEX piping plumbing systems will be allowed only during the time period of November 1 – April 30 and under the following conditions:

- Air testing pressures shall be a minimum of 40 psi and a maximum of 80 psi.
- In order to protect all the fittings, air testing pressures should be applied on the same day as the requested inspection and released immediately afterwards.
- All conditions and/or criteria contained in this policy may be modified at the sole discretion of the Building & Codes Department.

Steve Gunkel
(Signed)

10/3/18
(Date)

Reviewed for Compliance
Date: 10/3/18 *by*